

60M HOME PV

60-CELL MONOCRYSTALLINE MODULE





315 Wp

MAX POWER OUPUT

19.1%

MAX EFFICIENCY

10 YEAR

PRODUCT WARRANTY

25 YEAR

LINEAR PERFORMANCE GUARANTEE

GUARANTEED POSITIVE POWER SORTING: [-0: +4.99 WP]



AVAILABLE IN 1000V OR 1500V SYSTEM VOLTAGE RATING



MANUFACTURED FOLLOWING INTERNATIONAL QUALITY SYSTEM STANDARDS: ISO9001



H-BLACK INTEGRATION AVAILABLE (ALL-BLACK MODULE)

HELIENE INC. IS A PREMIER SOLAR MODULE MANUFACTURER, SERVICING THE GROWING SOLAR ENERGY MARKETS OF NORTH AMERICA.

COMBINING PROVEN EUROPEAN TECHNOLOGY WITH NORTH AMERICAN INGENUITY ALLOWS HELIENE TO MAKE A REAL COMMITMENT IN PROVIDING SMARTER ENERGY CHOICES FOR THE FUTURE.


HELIENE

www.heliene.com


LINEAR PERFORMANCE GUARANTEE

10 YEAR WORKMANSHIP WARRANTY • 25 YEAR LINEAR PERFORMANCE GUARANTEE


Ours Industry Standard



DIMENSIONS FOR 60M HOME PV SERIES



I-V CURVE FOR HELIENE 60M HOEM PVSERIES



CERTIFICATIONS





ELECTRICAL DATA (STC)

Peak Rated Power	P _{mpp} (W)	315	310	305	300
Maximum Power Voltage	V _{mpp} (V)	33.44	33.90	33.44	33.40
Maximum Power Current	I _{mpp} (A)	9.66	9.58	9.20	9.13
Open Circuit Voltage	V _{oc} (V)	40.13	39.89	39.98	39.83
Short Circuit Current	Isc (A)	10.22	10.11	9.68	9.59
Module Efficiency *	Eff (%)	19.09	18.78	18.48	18.18
Maximum Series Fuse Rating	MF (A)	20	20	20	15
Power Output Tolerance	lerance [- 0 , + 4.99] Wp				

STC - Standard Test Conditions: Irradiation 1000 W/m2 - Air mass AM 1.5 - Cell temperature 25 °C

* Calculated using maximum power based on full positive output tolerance [-0, +4.99] Wp

MECHANICAL DATA

Dimensions (L x W x D)	1666 x 1001 x 40 mm (65.5 x 39.4 x 1.6 inch)	
Weight*	22 kg (48.5 lbs)	
Output Cables	1.0 m (39.4 inch) symmetrical cables with MC4 type connectors	
Junction Box	IP-67 rated with bypass diodes	
Frame	Double webbed 15 micron anodized aluminum alloy	
Front Glass	Low-iron content, high-transmission PV solar glass	
Solar Cells	60 Monocrystalline cells (159 x 159 mm)	

* Calculated using 3.2mm PV glass, if 4mm profile is requested weight load will vary

CERTIFICATIONS

UL Certification	ULC/ORD-C1703-1, UL1703
IEC Certification	Optional

All Heliene modules are certified under the California Energy Commision (CEC) Listing Report

TEMPERATURE RATINGS

Nominal Operating Cell Temperature (NOCT)	+45°C (±2°C)
Temperature Coefficient of P_{max}	-0.38%/°C
Temperature Coefficient of $V_{\mbox{\tiny oc}}$	-0.36%/°C
Temperature Coefficient of I _{sc}	0.07%/°C

MAXIMUM RATINGS

Operational Temperature	-40°C - +85°C	
Max System Voltage	1000V (*1500V)	
	*Optional	

WARRANTY

10 Year Manufacturer's Workmanship Warranty 25 Year Linear Power Guarantee

(Refer to product warranty page for details)

PACKAGING CONFIGURATION

Modules per box:	26 pieces
Modules per 53' trailer:	936 pieces

HELIENEGOM_HOME PV-Rev.01





